

PROJECT: Mill Creek 161-kV Transmission Line Project
 PREPARED BY: KAK/JLT, Senga, Inc.
 DOCUMENT: Engineering Opinion of Cost
 DATE: 6-Jul-2018
 REVISION: Rev 2 - BMCD

Rev. 0: Costs below are intended to account for 7.7 miles of OH Line Construction only. No costs are included that may additionally account for:
 a. Substation
 b. Any portion of the line that may be routed underground, distribution or otherwise.
 c. Existing 69-kV along route has been considered for double circuit.
 Rev. 1: update costs
 Rev. 2: remove wood tab per City, update costs

Design, 161-kV using Self-Supporting Steel Structures on Foundations, 7.7 Miles								
Item No.	Item	Foundations	Material - Pole	Material Assemblies	Construction T&D	Quantity	Subtotal per Structure	Notes
Structures								
1	Double Circuit Steel Dead End Structure	\$198,715	\$125,068	\$7,910	\$16,045	6	\$2,086,425	
2	Steel Running Angle (5-15)	\$83,695	\$31,470	\$1,375	\$9,525	12	\$1,512,783	
3	Double Circuit Steel Running Angle (5-15)	\$125,695	\$67,661	\$2,500	\$12,175	2	\$416,063	
4	Steel Running Angle (16-30)	\$94,855	\$45,419	\$1,525	\$8,235	6	\$900,202	
5	Double Circuit Steel Running Angle (16-30)	\$145,900	\$58,625	\$2,450	\$10,855	1	\$218,960	
6	Steel Tangent	\$400	\$24,553	\$1,375	\$9,525	52	\$1,864,950	Assumed direct embed foundation
7	Double Circuit Steel Tangent	\$400	\$46,708	\$2,500	\$12,175	10	\$617,834	Assumed direct embed foundation
	Subtotals -->	\$3,187,850	\$3,338,342	\$177,260	\$912,265	89	\$7,615,717	
Conductor & Shield Wire								
7	Conductor, 795 kcmil ACSR "Drake", 123,650-ft		\$197,840		\$727,500	1	\$925,340.00	
8	Shield Wire, 0.506" 24-Fiber OPGW, 41,200-ft		\$67,980		\$323,200	1	\$391,180.00	
9	Splice Boxes at Substations and Junction Points		\$8,000		\$2,865	4	\$43,460.00	4 locations for splice boxes
10	Misc.: Stringing Setups, Xings, Etc.		\$35,000		\$131,510	1	\$166,510.00	Est. LS for 7.7 mile design; Includes setups for stringing, contractor-provided guard structures for road & line xings, etc.
	Subtotals -->		\$332,820		\$1,193,670		\$1,526,490	
Other Construction-Related Costs								
11	Mobilization / De-Mobilization				Estimated Lump Sum Cost =		\$36,100	
12	Construction Yard Setup, Security, Material Storage				Estimated Lump Sum Cost =		\$298,450	
13	ROW Access, SWPPP				Estimated Lump Sum Cost =		\$366,040	
14	ROW Restoration				Estimated Lump Sum Cost =		\$171,935	
	Subtotals -->						\$782,505	
Summary of Material & Construction Costs Only =							9,142,207	
20% Material Contingency =							1,407,254	Also is intended to account for any markup costs (~10%)
30% Construction Contingency =							633,781	Contingency on Structure & Wire labor only: Construction costs may vary significantly based on market conditions, contractor availability, & overall schedule requirements
Subtotal with Contingencies =							11,183,242	
Per Mile Base Cost =							1,553,733	Divide previous "Subtotal with Contingencies" by 7.7 + Construction-Other costs by 7.7
Cost for 7.7 Mile OH Line, Base Cost =							11,963,747	Multiply previous "Per Mile Base Cost" by 7.7
Client-Mgmt Costs & Consultants (Engg, Public Involvement, Real Estate Assessment and Acquisition)								
15	Complete Engineering (Line Design, Fdtns, Constr Docs & Dwg)				% of Base Cost =	10%	\$1,196,375	
16	Surveying				Survey Lump Sum Cost =		\$40,000	Staking
17	Stakeholder Engagement & Public Relations				% of Base Cost =	8%	\$957,100	
18	Real Estate				% of Base Cost =	10%	\$1,196,375	
19	Proj Mgmt, Field Coordination & Inspection, Etc.				% of Base Cost =	8%	\$957,100	Assumes 12-week construction schedule w/ NO full-time on-site safety coordinator
20	EPC Construction Contract Adder				% of Construction Cost =	10.0%	\$352,022	Assume based on construction-labor, other-, & contingency cost only; Adder may +/- based on overall amount
21	Eng & Proj Mgmt				% of Base Cost =	2.5%	\$299,094	
	Subtotals -->						\$4,998,065	
ROW (Acquisitions & Permits)								
22	Title Searches				Estimated Lump Sum Cost =		\$50,000	
23	Acquisitions				Estimated Lump Sum Cost =		\$550,000	
24	Crossing Permits				Estimated Lump Sum Cost =		\$30,000	
25	Environmental Permits, SWPPP Preparation, Monitoring				Estimated Lump Sum Cost =		\$112,000	
	Subtotals -->						\$742,000	
Summary of PM, Engr, Surveying, & Geotech; and ROW, Permitting, Etc. Costs Only =							\$5,740,065	
10% Contingency =							\$574,006	
Cost for 7.7 OH Line, Total Project =							\$18,277,818	
Per Mile Cost =							\$2,373,743	